INSTALLATION OF AUXILIARY TRANSFORMER AT MCR2 UNIPORT.

S/N	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	50KVA Pole Mounted Transformer	1	Nos		
2	33kv Gang Isolator	1	Nos		
3	33kv D-Fuse	1	Nos		
4	Lighting Arrester Silicon	1	Nos		
5	100 Amps Feeder Pillar	1	Nos		
6	9 Feet Channel Iron	10	Nos		
7	Disc Insulator	12	Nos		
8	Tension Clamp	12	Nos		
9	Socket Adapter	12	Nos		
10	Bolts and Nuts (6,8,10,12) Each	10	Nos		
11	Square Washer	80	Pcs		
12	50mm Copper Wire	60	m		
13	150mm ACSR	300	m		
14	40 F Reinforced Concrete Pole	2	Nos	260,000	520,000
15	95mm ² 0.415 x LPE Cable	6	m		
16	70mm x 4C 0.145 x LPE Cable	20	m		
17	95mm Cable Lug	10	pcs		
18	70mm Cable Lug	10	pcs		
19	50mm Cable Lug	10	pcs		
20	EarthRod 26mm Heavy Duty	9	Nos		
21	Animal Dung and Charcoal (4 bags each)	8	bags	10,000	80,000
22	Labour				1,500,000
23	Total				N2,100,000